

Council	Project Name	Project Manager	Cost	Start	Description
PCC WWA	Thompson Grove WW pipeline renewals	Hijari Thakur (Motts)	500K-800K	Fri 28/09/18	Replacement of 660 m of 300mm dia existing wastewater mains by open excavation and pipe bursting.
UHCC WWA	Akatarawa Rd Wastewater Renewals	Malcolm Franklin	500K-1M	Tue 11/09/18	160m of open trench 225OD PE sewer installation in private property and river reserve plus 50m of pipe bursting of 225OD PE through existing 200 dia AC in road reserve, and ancillaries
PCC STW	Bypass Pipe and CBD Drainage	Tom Blagjoli	2M-5M	Mon 15/04/19	Lay 590 m of concrete class 4 pipe ranging in size from 1200mm dia up to 1800mm dia. Porirua.
UHCC STW	[DF/CF] Stream Gr Stormwater Upgrade	Phil Read (Calibre)	100K-300K	Mon 1/10/18	
PCC WAT	Zonal Pressure Reduction and Low level DMA partitioning (Warspite Avenue DMA)		0-100K	Fri 21/09/18	To install SCADA linked District Metered Area (DMA) meters with pressure transducers at 11 Keneperu Drive and 377 Warspite Avenue
WCC STW	Wallace St Corridor: Stormwater Network Renewal (from 6 Rolleston St to 36 Wallace St) (with WAT, WWA & STW)	Richard Hickman	100K-300K	Thu 9/08/18	Upgrade of the existing stormwater pipeline at the bottom of Rolleston Street and along Wallace Street to Hargreaves Street to 525mm dia.
UHCC WWA	Dowling Gr Wastewater Renewals	Kay Suresh	100K-500K	Sat 30/06/18	328m sewer pipe lining and 57m pipe bursting
UHCC STW	1-19 Pinehaven Road storm water upgrades	Sue Harrison	200K-600K	Mon 1/04/19	Waiting on brief
HCC WAT	Waterloo Wellfield Collector Mains Upgrade Stage 4 (Pilmuir St)	Summer Faulkner	1M-1.5M	Tue 3/07/18	Installation of seismic upgrades to eight Waterloo Wellheads, including flexible connections and reinforcement of well casing connections.
PCC WAT	Commercial water meter replacement	Craig Brown	100K-300K	Fri 16/11/18	Supply & installation of water meters and backflow mitigation measures at commercial properties within Porirua City.
WCC WWA	Wallace St Corridor WW Renewals (from Carrington St - Finlay Tce) (with WAT, WWA & STW)	Richard Hickman	500K-1M	Fri 3/08/18	Renewal of the existing 100/150mm dia sewers on Wallace Street and Finlay Terrace including two sections across private properties at 92 and 107 Wallace Street.
UHCC WAT	Bulk Meter Purchase/Install - (Fergusson Drive)		100K-200K	Tue 11/12/18	Bulk water meter replacements
WCC STW	[DF/CF] Stirling St (10-14), Adelaide Rd (493) Stormwater Renewal	Campbell Allan	200K-400K	Fri 21/06/19	Upgrade 120 m of existing 300mm EW pipes with 525mm Class 4 RCRU pipe.
HCC WWA	Wainuiomata Sewer Renewals - (Wood St, Faulke Ave, Burden Ave)	Thomas Apthorp	500K-1M	Mon 1/10/18	675m of 150mm dia sewer renewal by open trenching and CIPP lining.
WCC STW	[DF/CF] Apuka St Stormwater Upgrade	Calibre	100K-400K	Fri 15/06/18	Installation of 127m of 300mm RCRU Class 2 stormwater pipe, 3 new sumps and 7 manholes, and all associated work.
UHCC WWA	Pinehill Cres Wastewater Upgrades	Dugall Wilson	100K-400K	Mon 1/04/19	[No Pinehill tender. Stantec will not build a pipeline, but we can't do a PCR until negotiations with Rimutaka Prison are closed out, so Project Server doesn't yet reflect this.]
UHCC WAT	Akatarawa Rd Bridge Pipework Seismic Strengthening	Andrew Zhang	100K-300K	Wed 12/09/18	Two tenders. One for buried pipeworks (175m length of new DN225 PE100 wastewater pipe and 55m length of new DN225 PE100 wastewater pipe) second tender for bridge section (55m length of new DN225 CLS wastewater pipe and seismic resilience strengthening of the existing DN250 CLS water main)
PCC STW	Paremata School	Rob Jack (3WL)	\$0	Wed 9/01/19	
WCC WWA	[DF/CF] Rotoliti St to Trafalgar St Sewer Renewal	Michael Syred	100K-300K	Mon 18/06/18	Lay 250 mm dia PE sewer
HCC WAT	Taita Reservoir (Seismic Upgrade)	Sue Harrison	1M-1.5M	Fri 31/08/18	Seismic strengthening of reservoir – internal slab and beam works, external strengthening and safety upgrades
PCC STW	Mareroa School flooding improvements	Rob Jack (3WL)	100K-300K	Mon 4/02/19	Divert stormwater by reshaping the carpark and building a bund on the school field.
HCC STW	Beach Stormwater Outlets	Steven Kelliher	100K-400K	Wed 1/08/18	Installation of duckbill check valves at 11 sites for stormwater outlets on Hutt City beaches.
HCC WAT	Kingsley Reservoir (Seismic Upgrade)	Sue Harrison	900k-1.1M	Tue 2/04/19	Seismic strengthening of reservoir – internal slab and beam works, roof strengthening and safety upgrades
PCC WWA	Titahi Bay WW pipeline re-lining	Phil Read (Calibre)	100K-400K	Mon 1/04/19	850m of structural lining of 150mm diameter sewer main across eight different sites.
PCC STW	Wall Place (2 & 4)	Sue Harrison	500K-1M	Mon 27/05/19	Stormwater improvements, flow diversion. Low flows to be maintained in existing open water channel to support eel habitat. Once level reaches 300mm in existing pipe, flow to be diverted to new storm water outfall discharge to Porirua Stream.
WCC WWA	[FWD] McCol St (22) to Mills Rd (18, also to 42); with Whau St (to 19), Mana St (to 28) and Fortunatus St Sewer Renewal	Hijari Thakur (Motts)	500K-800K	Mon 1/04/19	Rehabilitation by lining of 990m length 150mm dia wastewater pipes and 40m length 100mm dia wastewater pipes at various sites in Wellington City. Lay 14m 150mm dia by open excavation.
WCC STW	[FWD] Agra Cres (5-10A) Stormwater Renewal	Michael Syred	100K-300K	Tue 10/07/18	Replace 40m of 600mm dia stormwater pipe and ancillaries including a retaining wall.
HCC STW	Heketara St and Pukatea St Pipeline Upgrade (Eastbourne)	Michael Syred	100-300K	Fri 29/06/18	Redirection of sumps, stormwater mains and household laterals from the 900 mm stormwater mains to a 600 mm pipe, and allow the large main to be pressurised.
HCC WWA	Trunk Type B Network Development - Gibbon Street Trunk Main Upgrade	Josh Wright	1M-1.5M	Fri 4/05/18	570m of 425mm dia sewer main and manholes.
GWRC WAT	Gear Is UV Installation	Tristan Reynard	500K-800K	Thu 14/06/18	The purpose of this project is to upgrade the existing Gear Island Water Treatment Plant (WTP) with ultraviolet (UV) disinfection. The UV disinfection will provide a 3-log inactivation of protozoa and work in conjunction with the chlorine disinfection to mitigate public health risks associated with drinking water.
WCC WWA	[FWD] Hania St (3-18) to 60 Kent Tce Sewer Renewal	Tom Apthorp	100K-300K	Mon 1/04/19	150m of sewer renewal, including 150mm dia, 200mm dia and 300mm dia sewers.
WCC STW	[FWD] Newcombe Cres Stormwater Renewal & Johnsonville Road (28 to 33) High Capacity Sumps	Sue Harrison	100K-300K	Fri 1/02/19	Newcombe – 1 high capacity sump to be installed, 1 medium capacity sump to be installed. Broken pipeline in property 11 to be abandoned and grout filled. New pipeline to be installed on different alignment from existing manhole in property 11. Private lateral lines to be reinstated. Johnsonville – 2 to 3 high capacity sumps to be installed with direct connection to culvert under the road. Abandoned pipeline may be recommissioned depending on results from CCTV and modelling. Note detailed design has not started.
HCC STW	(Packaged) Melling and Rutherford Roads Stormwater Construction	David Crowther	1M-1.6M	Thu 12/07/18	Upgrade the 171 m long 1050mm NB Melling Road stormwater outfall (with 1600mm NB) and the 100 m long 600mm NB Rutherford Street stormwater outfall (with 1350mm NB), including automated penstocks, flapgates, and outlet structures.
HCC WAT	Korokoro Reservoir upgrade (Seismic Couplings, ASV and Triggers)	James Craig	0-100K	Fri 12/10/18	Seismic Coupling, ASV and Triggers
WCC STW	[FWD] Waikare St (4-7) Stormwater Renewal	Dugall Wilson	\$0.00	Mon 3/06/19	
UHCC WAT	Maymorn - PS Renewal incl. seismic strengthening (multiple primary goals)	Kama Slipeen	100K-300K	Fri 8/06/18	Construct a new pump station adjacent to the existing Maymorn pump station.
HCC WAT	Naenae Reservoir upgrade (Seismic Couplings, ASV and Triggers)	James Craig	0-100K	Thu 25/10/18	Seismic Coupling, ASV and Triggers
HCC STW	Victoria Street and Humes Street	David Crowther	500K-800K	Wed 6/02/19	Lay 270 m of stormwater pipe (pipe size TBC, primary sizes ranging from 450mm dia up to 1250mm dia.), and 100m of twin 375mm dia in Moa Street.
WCC WAT	Ngaio reservoir seismic improvements	Sue Harrison	1M-1.3M	Tue 5/02/19	Seismic strengthening of reservoir – internal slab and beam works, roof strengthening and safety upgrades
HCC STW	Whiorau Grove in Eastbourne	Michael Syred	0-100K	Fri 21/09/18	Installing additional sumps and reshaping the surface of Whiorau Grove.
PCC WWA	Duck Creek WWPS storage tank	Hijari Thakur (Motts)	500K-800K	Tue 26/03/19	Install underground storage tank adjacent to the pump station, consisting of 6 x 17m long 2m dia pipes.
WCC STW	Ross St (43-45) Stormwater Renewal (with Yule WW)	Steven Kelliher	\$0.00	Fri 28/06/19	Lay 150 m of stormwater pipe (pipe size TBC, primary sizes ranging from 450mm dia up to 1250mm dia.)
WCC WAT	Wallace St Corridor (Potable Water Network Renewals)	Richard Hickman	1M-3M	Fri 3/08/18	Renewal of existing 40mm, 50mm, 100mm dia water mains on Wallace Street and Finlay Terrace and replacement on a new alignment of the existing 100mm dia water supply pipeline on Hargreaves Street.
PCC WWA	Whitehouse Road - stages 3 and 4	Dugall Wilson	500K-1M	Tue 2/04/19	Renewal of 204m of U-shaped sewer (approximately 685mm x 1000m) by a mix of CIPP lining and open cut.
PCC WAT	Bath+ManaView Pipe Renewal	Michael Sheridan	100K-500K	Mon 1/04/19	Bath - 75m DN100 watermain and service connections, Mana View - 110m DN150 watermain, 60m DN100 watermain, 50m 63mm OD ridermain. Service connections.
HCC WAT	Cole St (Wheatley St to Waddington Dr) Network Renewals	Marketa Langova	100K-500K	Mon 18/06/18	245m of 125mm OD water main and 160m of 63mm OD water rider main pipe
PCC WWA	Tangere Dr WWPS Splitter Box	Leonard Wiles	200K-400K	Tue 15/01/19	Refurbishment work of the heavily corroded concrete flow splitter at the Tangere Drive WWPS.
HCC WAT	Cleland Cres (Seddon St to Seddon St) Watermain Renewal	Marketa Langova	500K-1M	Thu 31/01/19	438m of 180 OD water main pipe and 348m of 63 OD water rider main pipe
HCC WAT	Totara Street (6 to 76) Watermain Renewal	Marketa Langova	100K-500K	Fri 19/04/19	8m of 100 water main pipe and 590m of 63 OD water rider main pipe
PCC WWA	WWTP - Hydraulic improvements	Leonard Wiles	200K-500K	Thu 9/08/18	Increasing the inlet channel capacity to achieve a flow of 1,500/s to the aeration basin while maintaining an acceptable freeboard to the overflow weir. Currently the flow to the aeration basin is between 950 to 1,000/s. Upgrade depends on the preferred option for Aeration basin pipe. Likely to involve extending the weir and overflow collection channel an additional length along the inlet channel and overflow screening.
PCC WWA	WWTP - Milliscreen to Aeration Basin pipe	Leonard Wiles	600K-1M	Thu 9/08/18	Increasing the feed pipe capacity to achieve a flow of 1,500/s to the aeration basin while maintaining an acceptable freeboard to the overflow weir.
PCC WWA	WWTP - UV Treatment Upgrade	Mike Binns	500K-1M	Mon 3/06/19	Upgrade of UV treatment plant to accommodate 1500 l/s
WCC WAT	New Reservoir (POW) Omārōro Reservoir	Richard Hickman	20M-25M	Tue 29/01/19	800mm concrete lined steel (CLS) inlet on Hargreaves Street and 900mm CLS outlet pipelines from top of Hargreaves Street onto Wallace Street then onto Howard Street then connecting to existing bulk main on Tasman Street.
WCC WWA	Yule, Stoke, Tainui and Broomhedge Wastewater Renewals		500K-1M	Wed 22/08/18	Waiting on brief
GWRC WAT	Kaitoke Road Bridges Seismic Strengthening	Steven Kelliher	500K-1M	Fri 18/01/19	Kaitoke Road Access Bridges Seismic Strengthening at Pakuratahi River Bridge #1 & #2, and Farm Creek Bridge, including work on the abutments and new piles.
GWRC WAT	Ski-Club Resilience Upgrades	Tristan Reynard	10K-300K	Fri 1/03/19	Waiting on brief
WCC WAT	[FWD] Burma Rd (Station Rd to Malville St)	Michael Syred	1M-2M	Sun 1/07/18	Lay 600 m 200mm DICL water main in the carriageway of Burma Road and 170 m of 63mm OD PE100 SDR11 ridermain.
WCC WWA	PS12 Thorndon Quay North - Mechanical and Electrical Retrofit	Paul Winstanley	100K-200K	Fri 14/09/18	Remedial works required for wastewater pumping stations 12 (Thorndon Quay Nth), 23 (Byron Avenue) and 24 (Devonshire Road). This include the replacement of the pumps and modifications of the ventilation systems as well as other minor, routine remedial works
WCC WWA	PS23 Byron Street Mechanical and Electrical Refit	Paul Winstanley	100K-250K	Fri 14/09/18	Remedial works required for wastewater pumping stations 12 (Thorndon Quay Nth), 23 (Byron Avenue) and 24 (Devonshire Road). This include the replacement of the pumps and modifications of the ventilation systems as well as other minor, routine remedial works
WCC WWA	PS24 Devonshire Road Mechanical and Electrical Refit	Paul Winstanley	100K-250K	Tue 9/10/18	Remedial works required for wastewater pumping stations 12 (Thorndon Quay Nth), 23 (Byron Avenue) and 24 (Devonshire Road). This include the replacement of the pumps and modifications of the ventilation systems as well as other minor, routine remedial works
GWRC WAT	Ngauranga Reservoir Seismic Strengthening	Sue Harrison	2M-4M	Fri 3/08/18	Seismic strengthening of reservoir – External Ring Beams, tensioned ground anchors, roof connection and safety upgrades
GWRC WAT	Wainuiomata TWR seismic strengthening	Sue Harrison	1M-1.5M	Wed 26/06/19	Seismic strengthening of reservoir – internal slab and beam works, roof strengthening and safety upgrades
GWRC WAT	Porirua branch extend 450 steel to Conclusion St	Tristan Reynard	1M-1.5M	Mon 4/02/19	Extend 450 CLS
WCC WAT	[FWD] Marine Pde (Ferry St - Awa Rd) Network Upgrades [Firefighting and Growth]	Beth Parkin	1M-1.3 M	Mon 1/04/19	1120m of 150mm dia mPVC PN12 main and ancillaries.
WCC STW	SW Construction – Kibirnie Stage Two (Pump station construction)	Josh Wright	2M-4M	Wed 3/10/18	5 cumec SW PS and electrical building with ability to upgrade to 7.5 cumec. [Open market tender so shouldn't be on this list - assuming the intention is to circulate it publicly.]
WCC STW	Main Road 68 to 74 Tawa Stormwater Improvement	Jonathan Sanders	500K-800K	Wed 29/08/18	2 High capacity sumps to be installed on the West side of Main Rd, 1 high capacity sump to be installed on the east side. The sumps will drain to a proposed 900mm outfall into Porirua Stream.
WCC STW	Tawa School Stormwater Improvements	Mark Stanko	500K-800K	Wed 29/08/18	Overflow diversion of Redwood Stream at Tawa School into 15m open channel and 80m DN1200 RCRU pipe. Associated inlet and outlet works.
WCC WAT	Makara PS Pumps and Elec. Panels		100-300K	Tue 5/02/19	Pumps and Electrical panel replacements
WCC WAT	Russell Tce - Electrical Panel Replacement		100-300K	Thu 21/03/19	Pumps and Electrical panel replacements
WCC STW	[DF/CF] Kingsbridge Place (18 to Newlands College) Stormwater Upgrade (to fix 16A flooding)	Campbell Allan	100-300K	Fri 2/11/18	80 m 450mm dia PE pipe through private properties and overland within Pinkerton Reserve discharging to the stream.
WCC WAT	Montgomery PS Pumps and Elec. Panel		100-300K	Tue 9/04/19	Pumps and Electrical panel replacements
WCC STW	Oxford St (49) Stormwater Renewal	Sue Harrison	100-300K	Wed 1/05/19	Waiting on brief
WCC WWA	[FWD] Severn St (61-83) Wastewater Renewal	Beth Parkin	1M-1.2M	Mon 1/04/19	160m of 150mm dia sewer renewal in private property.